EXISTING UNDERGROUND HIGH VOLTAGE, SERIES CIRCUIT IN PROXIMITY TO ELECTROLIER. EXERCISE CAUTION WHEN INSTALLING NEW EQUIPMENT.

EXISTING OVERHEAD HIGH VOLTAGE AND COMMUNICATION LINES IN PROXIMITY TO PROJECT SITE. EXERCISE CAUTION WHEN INSTALLING NEW EQUIPMENT.

P-18831
C-3783
(CD 951B)
200W HPS
MSC III

CIRCUIT "5A" 82'

NEW COMBINATION TRAFFIC SIGNAL & MULTIPLE STREET LIGHTING SERVICE NO. 5
SP# 265849M
INSTALL: CIRCUIT "5A": 1 – 200W HPS LAMPS
CIRCUIT "5B": 5 – 250W HPS LAMPS

CIRCUIT "5B"

BIKE PATH

BUSWAY

AVE.

INSTALL 2" CONDUIT

CR=5'

CB

LADWP VAULT

P-25477
C-3783
(CD 951B)
200W HPS
MC III

P-26237
C-3783
(CD 929C)
200W HPS
MSC III

PARALLEL SERIES & MULTIPLE CONDUITS SHALL BE SEPARATED AT LEAST 4 FEET.

CR=25'

(1) P-25477
C-3783
(CD 953C7)
200W HPS
MC III

(3) P-26237
C-3783
(CD 929C)
200W HPS
MC III

EXISTING SERIES STREET LIGHTING CIRCUIT X-410 NO. 4
PP#130294M
EXISTING: 55 – 200W HPS LAMPS
13 – 100W HPS LAMPS
REMOVE: 4 – 200W HPS LAMPS
NEW LOAD: ____ kw

(37) P-18344
C-3783
(CD 951B)
200W HPS
MSC III

BURBANK BLVD.

FULTON AVE.

P-26237
C-3783
(CD 953C)
200W HPS
MC III
(1)

P-26237
C-3783
(CD 953C7)
200W HPS
MC III
(2)

P-26237
C-3783
(CD 929C7)
200W HPS
MC III
(3)

P-26237
C-3783
(CD 929C)
200W HPS
MSC III
(4)

EXISTING U.G. COMBINATION TRAFFIC SIGNAL & MULTIPLE STREET LIGHTING CIRCUIT NO. 6
EXISTING: 13 – 200W HPS LAMPS
REMOVE: 3 – 200W HPS LAMPS
INSTALL: 5 – 250W HPS LAMPS
1 – 200W HPS LAMP

P-25865
SL-4655
(CD 953C)
200W HPS
MSC III

EXISTING MULTIPLE STREET LIGHTING CIRCUIT
EXISTING: CIRCUIT "A": 5 – 200W HPS LAMPS
CIRCUIT "B": 5 – 200W HPS LAMPS
CIRCUIT "C": 8 – 200W HPS LAMPS
NO CHANGE

CIRCUIT "C"

EXISTING SERIES STREET LIGHTING CIRCUIT X-410 NO. 4
PP#130294M
EXISTING: 55 – 200W HPS LAMPS
13 – 100W HPS LAMPS
REMOVE: 4 – 200W HPS LAMPS
NEW LOAD: ____ kw

BURBANK BLVD.

FULTON AVE.

CIRCUIT DIAGRAM

N.T.S.

20' 10' 0 5' 10' 20'
1"=20'
GRAPHIC SCALE

SL-5945, W.O. L0120115

AS-BUILT RECORD DRAWING

CITY OF LOS ANGELES
BUREAU OF STREET LIGHTING

APPROVED _____ 20____

BY _____
DIRECTOR BUREAU OF STREET LIGHTING

REV	DATE	BY	APP	REG NO	EXPIRES	SEAL HOLDER	DESCRIPTION
1	02-16-06	AXK					AS-BUILT RECORD DRAWING
0	06-30-04	JFB	WJO	52655	12/31/06	WALTER J. OKITSU	ISSUED FOR CONSTRUCTION

DESIGNED BY J.BERNAL
DRAWN BY J.BERNAL
CHECKED BY D.YEH
IN CHARGE W.OKITSU
DATE 06/30/04

REGISTERED PROFESSIONAL ENGINEER
WALTER J. OKITSU
No. 52655
Exp. 12/31/06
CIVIL
STATE OF CALIFORNIA

LOS ANGELES COUNTY METROPOLITAN TRANSPORTATION AUTHORITY
SAN FERNANDO VALLEY EAST-WEST BRT PROJECT

WASHINGTON

SHIMMICK OBAYASHI JV

Katz, Okitsu & Associates
Traffic Engineers & Transportation Planners
1055 Corporate Center Drive, Suite 300
Monterey Park, California 91754-7642
Tel: (323) 260-4703 Fax: (323) 260-4705

NORTH HOLLYWOOD TO WARNER CENTER
GROUP 5 INTERSECTIONS
RESTORATION STREET LIGHTING
BURBANK BLVD./FULTON AVE.
& BUSWAY (SHEET 7 OF 10)

SEGMENT NO C0675
DRAWING NO G5SL-007
REV 1
SCALE 1" = 20'
SHEET NO