


INSTALL: PIPE (AETNA ST)
1025' - 6" x 0.31" DI-A PW CL RG PIPE
10 - 6" X 45° DI-A RG BEND (B-B)
2 - 6" X 250# DI-A RG GATE VALVE
GV#324, 663; GSM181-152

ABANDON:
1005' 6" C.I. PIPE PLR#37928(30), #10038(90)



USE VGX06 FOR ENGINEERING DESIGN IN CONJUNCTION WITH 8" MAINLINE / W.O.# VGX10	USE VGX06 FOR ENGINEERING DESIGN IN CONJUNCTION WITH 6" MAINLINE / W.O.# VGX07
USE VGX11 FOR 3" EQ. & SMALLER SERVICES RENEWALS & RETAPS IN CONJUNCTION WITH 8" MAINLINE / W.O.# VGX10	USE VGX08 FOR 3" EQ. & SMALLER SERVICES RENEWALS & RETAPS IN CONJUNCTION WITH 6" MAINLINE / W.O.# VGX07
USE VGX12 FOR 4" & LARGER SERVICES RENEWALS & RETAPS	USE VGX09 FOR 4" & LARGER SERVICES RENEWALS & RETAPS

WATER MAIN AND SEWER SEPARATION
NEW MAIN AND CONSTRUCTION
PROCEDURES EXCEED STATE D.P.H.
REQUIREMENTS FOR SPECIAL PIPE AS
PER "CRITERIA FOR THE SEPARATION OF
WATER MAINS & SANITARY SEWERS."

NOTES:

- USE TBS-CLSM FOR TRENCH BACKFILL.
- INSTALL 8 MIL POLYETHYLENE WRAP ON ALL D.I. & C.I. PIPE & FITTINGS.
- ALL VALVES ARE TO BE TAGGED UPON INSTALLATION.
- TRENCHING, BACKFILL AND PAVING TO BE PERFORMED PER STANDARD PLAN S-477-1.
- SLURRY TO BE PLACED TO BOTTOM OF FINAL PAVING EXEMPTION FROM S-477-1.
- CONCRETE PAVEMENT SHALL BE REPLACED PER GREENBOOK 2009, SECTION 300-1.3.2.

[illegible]